

香港中樂團工程招標公告

招標項目：為 2024 鼓樂節《鼓樂心弦 連結世界》5G 直播音樂會提供舞台, 燈光, Video Wall 等器材租借, 安裝及拆卸。

項目內容： 合約工程包括如下：

1	<u>3m x 3m Pagoda Marquee</u>	25	sets	HK\$
	- Color: White			
	- Include brushed aluminium frame with fascia foamboard, white PVC roof, side wall, water gutter, 1.2mW x 0.6mD x 0.76mH working table with table cloth x2, black folding chair x4, fan x1 and concrete block for counterweight			
2	<u>10m x 10m Tent</u>	2	sets	HK\$
	- Color: White			
	- Include brushed aluminium frame with fascia foamboard for VIP tent, white PVC roof, side wall, fan, concrete block for counterweight			
3	<u>3m x 3m Pop-up Marquee</u>	24	sets	HK\$
	- Color: White			
	- Including 10 sets for spare			
	- Include brushed aluminium frame with fascia foamboard, side wall, 1.2mW x 0.6mD x 0.76mH working table with table cloth x2, black folding chair x4, fan x1			
4	<u>5m x 5m Pagoda Tent</u>	1	set	HK\$
	- Color: White			
	- Include brushed aluminium frame with fascia foamboard, side wall, 1.2mW x 0.6mD x 0.76mH working table with table cloth x2, black folding chair x4, fan x1			
5	<u>License and Certifications</u>	1	job	HK\$
	- Registered Structural Engineer reports and certificates			
6	<u>Manpower & Transportation</u>	1	job	HK\$
	- Include sufficient manpower for set up & dismantle			
	- Include 2-way transportation & rubbish disposal			

香港中樂團工程招標公告

B	Furniture			
1	<u>Audience Chair</u>	200	pcs	HK\$
	- Color: White			
2	<u>1.8mW Metal Barrier</u>	400	pcs	HK\$
3	<u>Performers Chair</u>	100	pcs	HK\$
	- Banquet Chair in Black			
4	<u>Manpower & Transportation</u>	1	job	HK\$
	- Include sufficient manpower for set up & dismantle			
	- Include 2-way transportation & rubbish disposal			
C	Electricity			
1	<u>Electricity Item for Veune Setup</u>	1	job	HK\$
	- Include 500W socket, light tube and flood light			
2	<u>Power Generator</u>	2	sets	HK\$
	- 400Kva generator			
	- 2 days x genset fuel refill per day			
	**Estimated Diesel Cost			HK\$
3	<u>Power Distributions Power Distribution</u>	1	job	HK\$
	- 200A lug to camlok F (1C 95sqmm cable*5) 2.5m			
	- 200A camlok cable(1C 95sqmm cable*5) 30m			
	- 63A 5pin ceeform (5G16sqmm cable) 30m / pcs			
	- 32A 5pin ceeform cable(5G6sqmm Cable) 30m			
	- 32A 5pin ceeform cable(5G6sqmm Cable) 10m			
	- 16A 3pin ceeform cable (3G2.5sqmm cable) 30m			
	- 32A TPN to 3*32A SPN MCB DB (4U)			
	- 200A TPN distribution box			
	- 16A 3pin ceeform to 13A 2way socket			
4	<u>Manpower & Transportation</u>	1	job	HK\$

香港中樂團工程招標公告

	- Include sufficient manpower for set up & dismantle			
	- Include 2-way transportation & rubbish disposal			
D	Hardware Production			
1	<u>Main Stage - Stage Platform & Ground Support</u>	1	set	HK\$
	- 1 x Platform with carpet, size: 23mW x 18mD x 1.2mH			
	- 1 x Ground support system, size: 46mW x 18mD x 9mH			
	- 3 x Cam platform, size: 1.8mW x 1.2mD x 1mH			
	- Including Tap Dancing & Bare Foot Dancing Flooring Changing			
	- On Stage Riser			
	- 1 x Rain cover			
	- 1 x Mesh Banner on Stage			
	*Concrete blocks will be quoted separately upon the RSE calculation			
2	<u>24 Drum Stage - Stage Platform</u>	1	set	HK\$
	- 1 x Platform with carpet, size: 10mW x 7mD x 0.2mH			
	- 2 x Ramp Platform with carpet, size: 1.83mW x 1.83mD x 0.2mH			
	- 1 x Backdrop , size : 10mW x 2.4mH			
3	<u>Press Platform</u>	1	set	HK\$
	- 1 x Platform with carpet, size : 14mW x 2.44mD x 0.6mH			
	- Including handrails and staircase x 2 sets			
4	<u>Control Panel</u>	1	set	HK\$
	- 1 x Platform with carpet, size 15mW x 5mD x 2mH			
	- Marquee Cover Size 3m x 3m Pagoda Marquee x 4 sets			
	- Staircase x 2 at back			
	- Include concrete block			
5	<u>Info Display</u>	3	sets	HK\$
	- Size: 2mW x 2mD x 2mH			
	- Including graphic printing			

香港中樂團工程招標公告

6	<u>Main Entrance Archway</u>			
	- Size: 18mW x 3.5mH	1	set	HK\$
	- Include 2 banners printing			
7	<u>Entrance Archway</u>	1	job	HK\$
	- Size: 4mW x 3.5mH x 3 sets, 6mW*3.5mH x 1 set			
	- Include 2 banners printing			
8	<u>Flooring Protection</u>	1	job	HK\$
	- Flooring protection at the specific areas (Track for Cameras, Marquee, Light Tower, Control Panel, etc.)			
	- Delivery route			
	- Manpower for setup and dismantle			
	- Including Manpower Standby Onsite for Moving Around the Mates			
9	<u>Standing Platform for the Giant Drum</u>	1	job	HK\$
	- Stage at 0.6mH with staircase (2.4mW*2.4mD)			
	- 1 x Info Display Truss Size : 0.4mW*0.4mD*2.5mH			
10	<u>Manpower & Transportation</u>	1	job	HK\$
	- Include sufficient manpower for set up & dismantle			
	- Include 2-way transportation & rubbish disposal			
11	<u>Mechanisms (Forklift x 4, Crane x 4 days, Boomlift x 3)</u>			HK\$
E	<u>AV Equipment</u>			
1	<u>Lighting System</u>			HK\$
	- Arri Skypanel S60C	20	pcs	
	- Fineart 470 BSW	16	pcs	
	- Fineart 4099 Moving Wash	20	pcs	
	- 4 Head Molefay	12	pcs	
	- Motors	12	sets	

香港中樂團工程招標公告

	- Operator Standby	1	job	
	- Technician	6	pax	
2	<u>Video System</u>			HK\$
	- Outdoor LED wall at size 7mW*4mH	2	sets	
	- LED wall at the back of Control Panel, size at 12mW*3mH	1	set	
	- Analogway Pulse 2	1	set	
	- Control & Accessories	1	job	
	- Operator Standby	1	job	
	- Technician	4	pax	
3	<u>Light Tower</u>	2	sets	HK\$
	- Size : 2mW x 2mD x 8mH			
	- Including Lighting Equipment			
4	<u>Equipment</u>			HK\$
	- Music Stand and Lights	100	sets	
5	<u>Technical Crew</u>	1	job	HK\$
	- Technicians Standby			
	- Manpower for Setup and Dismantle			
F	<u>Office Container</u>			
1	<u>20' Movable Container Office</u>	11	nos	HK\$
	- Including AC, 1.8mW x 0.6mD x 0.76mH Working Table x 3, Black Folding chair x 6			
	- Include 2-way Transportation & Installation			
G	<u>Event Management</u>			
1	<u>Pre-event Programme Management</u>	1	job	HK\$
	- Overall Creatives, Conceptualization and Execution			
	- Dedicated Project Team for Overall Project Management & Coordination for Pre-event, On-site and Post Event			
	- Preparation and Monitoring of Overall Project Timeline			

香港中樂團工程招標公告

- Arrange and Attend Pre-event Meetings, Site Inspections and Technical Tests			
- RSE Calculation, Extinguishers, Emergency Lightbox and Exit Lightbox			
- Liaison with Relevant Parties			
		Grand Total:	HK\$

招標圖紙：請將公司名稱、商業登記證、聯絡人、聯絡人職稱及電話，電郵至 cynthia@hkco.org 索取。

預計施工期：2024 年 12 月 2 日至 8 日

演出日期：2024 年 12 月 8 日

拆卸日期：2024 年 12 月 9 日

施工地點：西九文化區藝術公園

項目負責：舞台技術及製作高級經理 曾浩然先生

電話：852-3185 1642

電郵：ray@hkco.org

截標日期：2024 年 11 月 25 日(星期一)中午 12 時

投遞標書：投標者必須提供圖紙及按招標書內指定物資提供報價，如未能提供相同物料必須清楚說明替代物料資料。投標書放置信封內密封，並在信封封面清楚註明「香港中樂團工程招標 2024」，並於 **11 月 25 日(星期一)中午 12 時前**把投標書放入香港上環皇后大道中 345 號上環市政大廈 7 樓行政部門外投標書箱內。投標者必須在截標時間前把投標書放入本招標箱內。**逾期遞交或未有放入指定投標箱的投標書，概不受理**

香港中樂團工程招標公告

備註： 所有使用之物料、式樣及內容，須於施工前與香港中樂團確認。
香港中樂團不一定採納任何一份投標書，即使該份投標書索價最低。
香港中樂團有權與任何投標者商議批出合約的條款。